# The Progress of Osaki CoolGen Project

Fourth International Conference on Carbon Recycling September 26, 2022 **Osaki Coolgen Corporation** https://www.osaki-coolgen.jp/en/



## **Company Profile**





## Osakikamijima



### **Carbon Recycling in CCUS**

Coolgen Project.



3

• Carbon Recycling: Focusing on utilization of CO2, in order to contribute to the energy security issues as well as climate change problems by innovative R&D with industries, academia and public from all over the world.



Reference: Roadmap for Carbon Recycling Technologies (Ministry of Economy, Trade and Industry)

### **Outline of Osaki CoolGen Project**



- For the realization of innovative low carbon coal-fired power generation in which IGFC, an ultimate high-efficiency power generation technology, is combined with CO<sub>2</sub> capture in order to significantly reduce CO<sub>2</sub> emission from coal-fired power generation.
- The project is to be implemented in three steps. Step 1 was implemented from FY2012 as a subsidized project of the Ministry of Economy, Trade and Industry and Step 2 has been implemented since FY2016 as a NEDO subsidized project.





### **Step 1 : Schematic operation flow of oxygenblown IGCC demonstration units and facilities**





### **Characteristics of Gasifier : High Gasification Efficiency**





# Demonstration Targets and Results (Step1)



Items	Targets	Results
Plant efficiency	Net efficiency 40.5% (HHV)	Net efficiency 40.8% (HHV)
Emission level	<ul> <li>SOx : 8ppm</li> <li>NOx : 5ppm</li> <li>Particulate : 3mg/m<sup>3</sup>N</li> <li>(O2 equivalent 16 %)</li> </ul>	<ul> <li>SOx : &lt;8ppm</li> <li>NOx : &lt;5ppm</li> <li>Particulate : &lt;3mg/m<sup>3</sup>N</li> <li>(O2 equivalent 16 %)</li> </ul>
Coal variety compatibility	Applicable to various types of coal	<ul> <li>Verified with four kinds of coal (including design coal)</li> <li>Achieved</li> </ul>
Reliability	Commercial-level annual plant availability of 70% or higher (5,000 hours endurance test)	<ul> <li>Endurance test 5,119h (accumulated)</li> <li>Continuous operation 2,168h</li> <li>Achieved</li> </ul>
Flexibility	Commercial-level (Load change rate of 1-3%/min)	<ul> <li>Load change rate ~16 %/min</li> <li>Minimum load 0MW(net)</li> <li>Achieved</li> </ul>
Economy	To obtain a prospect of the equivalent or less generating cost with commercial PCF plant	Obtained a prospect of equivalent generating cost with commercial PCF plant

# The role of thermal power in the introduction of a large amount of renewables



8

# The impact in the introduction of a large amount of renewables

During period of low demand, there is a big difference of status of power demand and supply between May 2 (weekday) and May 3 (holiday).

#### Status of power demand and supply in Kyushu



Source: KYUSHU ELECTRIC POWER TRANSMISSION AND DISTRIBUTION CO., INC., Power usage in Kyushu (from April 2018 to June 2018)

# For introduce of a large amount of unstable renewables

- For stable of power system, there are thermal powers, pumped storage powers, and interconnect lines.
- Especially, thermal powers takes an important role of load adjustment.



Thermal powers are required not only high efficiency, but flexible operation.

- Improvement of load change rate
- Lower minimum load

Pumped storage

Solar

Hydro

Wind

Thermal

Biomass

Nuclear

Geothermal

Interconnected line

Area demand

Shortening of startup time

# Step 2: Outline of Demonstration Test Plan

OSAKI COOLGEN 9

To verify technical capability of the IGCC plant to stably maintain high power generation efficiency and stably separate  $CO_2$  even when the IGCC plant is combined with  $CO_2$  capture demonstration facilities.



Outline of the CO <sub>2</sub> capture demonstration facilities				
Demonstration scale	CO <sub>2</sub> recovery from IGCC gas with a recovery rate of 15%			
CO <sub>2</sub> absorption and regeneration method	Physical absorption method			
CO shift method	Sweet shift method (gas extraction after desulfurization)			
Basic performance	$CO_2$ recovery rate: 90% or more Purity of recovered $CO_2$ : 99% or more			

Sour shift catalyst test facilities			
CO shift method	Low temperature sour shift method (gas extraction before desulfurization)		

Schematic operation flow of the Step 2 demonstration system

### Oxygen-blown IGCC with CO<sub>2</sub> capture : Pre-combustion CO<sub>2</sub> capture



Compared to captured CO2 from the emitted gas by Post-combustion method, Pre-combustion method can efficiently capture CO2 with little energy losses because syngas before combustion has high CO2 concentration and high pressure with less processing gas.



## **CO2 Capture Technology Roadmap**



CO<sub>2</sub> separation and capture cost

High

#### Chemical absorption method



use a solvent, such as amine. Separation and capture cost: 4200 yen/t-CO<sub>2</sub>

#### Utilization of CO<sub>2</sub>



This technology utilizes captured CO<sub>2</sub> to produce valuables such as alternatives to oil and chemical raw material

#### Solid absorbent method



reduces energy requirement and separate CO<sub>2</sub> by combining amine, etc.

#### Membrane separation method

separates by using

a membrane which penetrates CO<sub>2</sub>

selectively.

#### Storage of CO<sub>2</sub>



Low

To store separated and captured CO<sub>2</sub> under ground. practical realization of CCS technology by around 2020.

The plant for this business is under construction, and the storage will be initiated in 2016.

\* The cost prospect in the Figure was estimated based on various assumptions at present.

**Development Target** Physical absorption



#### method



CO<sub>2</sub> absorbed into a physical absorption solution under high pressure.

Around 2020

Separation and capture cost: Approximately 2000 yen level/t-CO<sub>2</sub> Around 2020

#### **Ciused IGCC**

the oxygen fuel technology to the IGCC technology.

Present

Source : Technology road map for next generation thermal power generation (METI)

Around 2030

# **CO2 Capture Unit**





### **Demonstration Targets and Progress**



Practical realization of a commercial scale plant through the demonstration of the system using the large-scale demonstration facilities with oxygen-blown IGCC combined with  $CO_2$  capture facilities

Items	Targets	Results		
Basic performance	<ul> <li>CO<sub>2</sub> recovery rate : 90% or more</li> <li>Purity of recovered CO<sub>2</sub>: 99% or more</li> </ul>	<ul> <li>CO<sub>2</sub> recovery rate : 90% or more</li> <li>Purity of recovered CO<sub>2</sub>: 99% or more</li> <li>Achieved</li> </ul>		
	The prospect of net efficiency 40% with capturing 90% of $CO_2$ in a commercial-scale plant (1500°C class IGCC)	Conduct the additional demonstration test on various operating conditions to optimize process During verification		
operability and reliability	Establishment of the operation method of IGCC with $CO_2$ capture and verification the reliability	<ul> <li>Established the method of start-up and stop of IGCC with CO<sub>2</sub> capture</li> <li>Verified with two different coals</li> <li>During verification</li> </ul>		
economic efficiency	Evaluation of the cost per amount of recovered $CO_2$ in the commercial-scale IGCC plant using cost target data shown in the technology roadmap <sup>*2</sup> as a benchmark.	Evaluate after the demonstration test During verification		
*1 The power generation efficiency includes CO <sub>2</sub> capture process (except power for CO <sub>2</sub> storage)				

\*2 Technology roadmap for next-generation thermal power generation (METI, June 2015)

## CO<sub>2</sub> supply from CO<sub>2</sub> capture unit



High quality CO<sub>2</sub> is supplied to tomato cultivation. and Carbon recycling RD&D users from the CO<sub>2</sub> capture unit attached to the oxygen blown IGCC demonstration test facility of



Carbon recycling demonstration base

#### Promotion project on establishment of the Center



Carbon Recycling 3C initiative, as a Japan policy, is decided to establish the Center of Research at Osakikamijima town, Hiroshima prefecture where CO<sub>2</sub> can be captured now.



Osaki Courgen has started the "Project to Promote the Effective Use of CO2" as a NEDO commissioned project, and has completed the development of its R&D base, and has been supplying CO2 since June 2022.

# Thank you for your reading



We would like to express our gratitude to the Ministry of Economy, Trade and Industry (METI), and the New Energy and Industrial Technology Development Organization (NEDO) for continuous support to the Osaki CoolGen Project. We will carry on design, construction and demonstration steadily and safely, and make our best effort to achieve successful completion of the Osaki CoolGen Project.



■ This ppt may not be reproduced in whole or in part without the permission.